Tele : 0291- 2510559 (civ)
: 6931 (mil)
e-mail : apsjodhpur1992@gmail.com

Army Public School
Near FOL Depot
Ajmer Road
Jodhpur (Raj) – 342 010

10792/APSJ/Accts(ii)

02 Jan 2025

CALL FOR QUOTATION

Sir,

1. We would like to carry out Renovation Work of Vice Principal Office. The details of the same is enclosed as Appendix.

2. Total cost (including all taxes) to be mentioned should be all inclusive. No additional payment will be made.

3. 5% of the total cost will be retained in the form of Joint FD/Bank Guarantee as security deposit by the final bidder and the same will be refunded on completion of one year/warranty period.

4. Firm to ensure work to be executed as per above scope of work.

5. All quotation documents will be signed by the authorized firm's representative and firm's rubber stamp will be affixed on all the pages of the documents including envelope in which the quotation document will be sealed.

6. "Quotation for **"Renovation of Vice Principal Office"** will clearly be mentioned on top of the envelope.

7. Payment will be made by cheque after verification by the Project Management Group.

8. Photocopy of GST Registration and PAN Card will be attached with the quotation.

9. Firms to mention their full address with telephone number on the envelope.

10. Time Period for execution of job - Within 30 days on issue of supply -cum work order.

11. If the requisite items will not be supplied in the prescribed period ie 30 days, then firm has to apply in writing with valid reasons for extension of supply period which will be accorded by the chairman for 5 days only, thereafter necessary penalty will be levied as under :-

(a) 1% Liquidated Damages will be deducted upto 10 days.

(b) Thereafter 2% penalty will be levied for every 10 days or part thereof.

12. Written request seeking any extension in PDC should came to Chairman minimum 7 days in advance with valid reasons. The extension of PDC can be accorded by Chairman for 5 days only. Decision on grant of extension in PDC will entirely be at the sole discretion of Chairman.

13. **Pre-Bid Meeting/Interaction**. A pre bid meeting/interaction will be held for all interested vendors on **08 Jan 2025** at 1100 hr at Army Public School, Jodhpur. Pre Bid meeting attendance is **compulsory** for all participating bidders for the said quotation.

..... 2/-

14. In view of the above, you are requested to intimate your quotation. Your quotation in a sealed cover addressed to the Principal, Army Public School Jodhpur should reach this office by 1100 hrs on **13 Jan 2024**. The quotation will be opened at **1115** hrs on **13 Jan 2024**.

(Dr (Mrs) Tabassum Khan)
Principal

To be filled by the Firm before Submission of Quotation

Name & address of the firm	:	_____
		_____
TIN No (Compulsory)		_____
GST No (Compulsory)	:	_____
Name of the Firm's owner/Rep		_____
Signature of the firm's owner/rep with seal	:	_____
Telephone & Mobile No	:	_____
E-mail address of the Firm	:	_____
Date of Depositing of the Quotation	:	_____

Appendix

RENOVATION OF VICE PRINCIPAL OFFICE

S.No	Scope of Work	Auth Unit	Qty	Rate Per Sqft/ Nos	Total Cost	Remarks
	False ceiling					
1	(23'x23')providing and fixing false ceiling at all height with saint –gobain board with Gobain expert channel as per design and pattern, to be laid in true horizontal and vertical level bottom to bottom distance 3 feet, cross patti on every 2 feet, every support between 2 feet with other raw material like fastener size – 6mm, screw size – 25 mm, channel 24 gauge, connecting clips and socket clip in channel.	Sqft	529			
	LIGHTS					
2	(23'x23')(Round panel light, Natural white) Cob &panels-neptune ,lotus,gold medal or equivalent . Wires –polycab or havells or equivalent	Sqft	529			
3	Wiring for 250 volts single phase and neutral 1X6 amps switched socket outlet (Primary Point) with 3X1.5 sq.mm PVC insulated copper conductor 1100 volts grade stranded flexible FRLS wires in concealed or surface mounted 25 mm dia PVC conduit and earthing the third pin of each socket outlet complete as per specification and as required.all kind of wiring will include in it.,existing unwanted wires would be remove,lan wiring will shift according to layout.					

	Vinyl Blinds					
4	2 WINDOW -Window customize vinyl blinds The Blind system consist of a coated aluminium tube of 38 mm diameter with provision of fabric clamping. The Fabric is rolled up and down through a chain drive system with built in drive gear and an over run brake system. The side brackets are universal type suitable both for wall and ceiling mounting. The bottom end of the fabric is rolled over an oval shape aluminium tube with provision to lock the fabric.	Sqft	91			
	PAINT					
5	paint: Suppying and applying 2 coat of putty ,one coat primer, and painted with 2 coat of plastic emulsion paint after cleaning the surface .BURGER /ASIAN / EQUIVALENT	Sqft	2645			
6	Provinding and fixing frosted glass door: in paint finish with 8mm Frosted glass auto door closer.Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, and any necessary hardware items with iso mark.	Nos	2			
	Total					
	GST					
	Grand Total					