ARMY PUBLIC SCHOOL JODHPUR

CIRCULAR

AMENDMENTS IN SCOPE OF WORK AND FINANCIAL BID – CONSTRUCTION OF SYNTHETIC HANDBALL COURT

1. Please refer open tender advertisements/uploaded on the school website and Pre Bid Meetings held on 26 Nov 2024 in respect of the subject project.

2. The following amendments may please be carried out in above tender documents :-

S. No	Detail of Amendments	Remarks
(a)	Revision of Scope of Work & Financial bid	Revised Scope of Work & Financial Bid being uploaded on the school website.

3. Rest no change.

4. Please submit the tender documents as discussed during the Pre Bid meeting and as per Revised Scope of Work/Financial Bid by due date.

ARMY PUBLIC SCHOOL, JODHPUR आर्मी पब्लिक स्कूल, जोधपुर

Date : 04 Dec 2024

(Dr (Mrs) Tabassum Khan)
Principal

_____
(Concerned Vendor)

SECTION IV

FINANCIAL BID

CONSTRUCTION OF SYNTHETIC HANDBALL COURT

S.NO.	ITEM DESCRIPTION	UNIT	QTY	Rate Per Sq ft /Pc	Total Amount
1	**Asphalt Base**	Sqmtr	1125		
	(a)Levelling of soil (Ground / Work Area) (b) Total Area – 24 x 44 Mtr = 1056 Sqmtr (c) Playing Area – 20 x 40 Mtr = 800 Sqmtr (d) Application of weed killer and soil Stablizer by using the chemicals (Gammaxene & Chloro Phyrophus) (e) Laying of WBM Hard Stone soiling course 6 ". (f) Compaction of the sub base/Layer by using 8-to-10-ton roller. (g) The Ground to be sloping 1" to 5" from Centre line toward edge (h) Laying of Asphalt BM in 80/100 Grade Bitumen for 30mm thickness in 10-19 mm stone aggregate. (j) Laying of Asphalt BC in 80/100 Grade Bitumen for 30mm thickness in 10-19 mm stone aggregate. (k) Providing and construction open storm water drain on (20 mtrs). Both or single side depending on the site conditions for effective drainage of rain water having of depth of 12 " and thewidth of 9 " with slope of 1 : 120 finished granting MS gratings on top. (l) Toe wall on all the four sides as retaining wall for the asphalted surface , up to a depth of 2 / 1 ' width 9 " and plaster only theexposed wall section and painted.				
	Chain Link Fencing				
2	Perimeter to be covered. Fabricate all round fences 10' in height and covering. With one opening in the form one gate. Fencing details. MS pipes at base, and top, 2" x 2" GI Chain Link Jaali of 12 gauge All pipes are 1 ½" ID of 16 gauge.	R mtr	131.6		
	Synthetic All weather Acrylic Surface				
3	Ultra cushion System (8-Layer) (a) 1 Layer of Filter/ Resurfacer. (b) 2 Layer of Heavy Cushion (c) 3 Layers of Fine Cushion. (d) 2 Layers of colour. (e) Court line Marking.	Sqmt	1056		
	Score Board With Stand				
4	Type - LED ,Colour - Red/Green, Digit Size - 6" , Dimmer - Yes , Captions- Down & Qtr, Clock, Home, Away & to go , Power Rating - 210 to 240 Vac ,Cabinet - All Cabinets are finished with 22-24 gauze CRC Mild Steel powder coating to ensure minimal Fading for the life of score board. Dimensions - 1225 x 815 x 60MM	Nos	1		
	Handball Ground Accessories complete with supply ans installation and its accessories.				
5	(a)Renovation or replacement(if Required)of Handball Goal Post:- Made of 70-80mm square section with all necessary items as required.	Nos	1		
	(b) Table for Jury Member (Stainless Steel 3' x 2').	Nos	2		
	(c) Player Bench (Stainless Steel 1.5' x 5' with Back Rest)	Nos	4		
	(d) stop watch(casio/titan/Equivalent)	Nos	1		
	Seating Arrangement.				
6	(30)silver Stainless Steel fixed Chair for seating .(Neelkamal/ Equivalent)	Nos	30		
7	1 feet parapet boundary (stepped footing 2feet deep and 1 feet above ground level, with finish plastered and paint)	Cuft	900		

8	shede : 2 iron shed (8'x20') with 15' height P/f of canopy made up of structural steel(MS I-section, channel, base plate, angle purlin etc.) with fibre profile heet at the top with necessary civil work such as painting & priming over structural steel, grouting of structural steel column in 1:2:4, raised kota flooring having kota 18- 20mm, raised 50mm from the ground level, side full brick wall 230mm with PCC 1:5:10 at the base, and provisions for electrical fixtures like conduiting, wiring, etc.FABRIC 900 GSM PVDF COTED.	Sqft	320		
	Amount				
	Add: GST (@18%of amount)				
	Total Amount				

Principal
APS Jodhpur

PRINCIPAL
आर्मी पब्लिक स्कूल
Army Public Schoo
जोधपुर / Jodhpur

To be filled by the Firm before Delivery

Name & address of the firm : _____

GST No (Compulsory) : _____

Name of the Firm's owner/Rep : _____

Signature of the firm's owner/rep with seal : _____

Telephone & Mobile No : _____

E-mail address of the Firm : _____

Annexure G

SECTION III

SCOPE OF WORK : CONSTRUCTION OF SYNTHETIC HANDBALL COURT

S.NO.	ITEM DESCRIPTION	UNIT	QTY	Compliance (To be filled by the Vendor)
1	**Asphalt Base**	Sqmtr	1125	
	(a)Levelling of soil (Ground / Work Area) (b) Total Area – 24 x 44 Mtr = 1056 Sqmtr (c) Playing Area – 20 x 40 Mtr = 800 Sqmtr (d) Application of weed killer and soil Stablizer by using the chemicals (Gammaxene & Chloro Phyrophus) (e) Laying of WBM Hard Stone soiling course 6 ". (f) Compaction of the sub base/Layer by using 8-to-10-ton roller. (g) The Ground to be sloping 1" to 5" from Centre line toward edge (h) Laying of Asphalt BM in 80/100 Grade Bitumen for 30mm thickness in 10-19 mm stone aggregate. (j) Laying of Asphalt BC in 80/100 Grade Bitumen for 30mm thickness in 10-19 mm stone aggregate. (k) Providing and construction open storm water drain on (20 mtrs). Both or single side depending on the site conditions for effective drainage of rain water having of depth of 12 " and thewidth of 9 " with slope of 1 : 120 finished granting MS gratings on top. (l) Toe wall on all the four sides as retaining wall for the asphalted surface , up to a depth of 2 / 1 ' width 9 " and plaster only theexposed wall section and painted.			
	Chain Link Fencing			
2	Perimeter to be covered. Fabricate all round fences 10' in height and covering. With one opening in the form one gate. Fencing details. MS pipes at base, and top, 2" x 2" GI Chain Link Jaali of 12 gauge All pipes are 1 ½" ID of 16 gauge.	R mtr	131.6	
	Synthetic All weather Acrylic Surface			
3	Ultra cushion System (8-Layer) (a) 1 Layer of Filter/ Resurfacer. (b) 2 Layer of Heavy Cushion (c) 3 Layers of Fine Cushion. (d) 2 Layers of colour. (e) Court line Marking.	Sqmt	1056	
	Score Board With Stand			
4	Type - LED ,Colour - Red/Green, Digit Size - 6" , Dimmer - Yes , Captions- Down & Qtr, Clock, Home, Away & to go , Power Rating - 210 to 240 Vac ,Cabinet - All Cabinets are finished with 22-24 gauze CRC Mild Steel powder coating to ensure minimal Fading for the life of score board. Dimensions - 1225 x 815 x 60MM	Nos	1	
5	**Handball Ground Accessories complete with supply ans installation and its accessories.**			
	(a)Renovation or replacement(if Required)of Handball Goal Post:- Made of 70-80mm square section with all necessary items as required.	Nos	1	
	(b) Table for Jury Member (Stainless Steel 3' x 2').	Nos	2	
	(c) Player Bench (Stainless Steel 1.5' x 5' with Back Rest)	Nos	4	
	(d) stop watch(casio/titan/Equivalent)	Nos	1	

	Seating Arrangement.			
6	(30)silver Stainless Steel fixed Chair for seating .(Neelkamal/ Equivalent)	Nos	30	
7	1 feet parapet boundary (stepped footing 2feet deep and 1 feet above ground level, with finish plastered and paint)	Cuft	900	
8	shede : 2 iron shed (8'x20')with 15' height P/f of canopy made up of structural steel(MS I-section, channel, base plate, angle purlin etc.) with fibre profile heet at the top with necessary civil work such as painting & priming over structural steel, grouting of structural steel column in 1:2:4, raised kota flooring having kota 18- 20mm, raised 50mm from the ground level, side full brick wall 230mm with PCC 1:5:10 at the base, and provisions for electrical fixtures like conduiting, wiring, etc.FABRIC 900 GSM PVDF COTED.	Sqft	320	

Principal
APS Jodhpur

PRINCIPAL
Army Public Schoo
जोधपुर / Jodhpur

To be filled by the Firm before Delivery

Name & address of the firm : _____

GST No (Compulsory) : _____

Name of the Firm's owner/Rep : _____

Signature of the firm's owner/rep with seal : _____

Telephone & Mobile No : _____

E-mail address of the Firm : _____