Tele : 0291- 2510559 (civ)
: 6931 (mil)
e-mail : apsjodhpur1992@gmail.com

Army Public School
Near FOL Depot
Ajmer Road
Jodhpur (Raj) – 342 010

10792/APSJ/Accts(iv)

18 Feb 2025

CALL FOR QUOTATION

Sir, corps

1. We would like to construct a Cricket Practice Pitch and Renovation of Existing Cricket Pitch. The details are as under :-

S.No	Nomenclature	A/U	Qty	Cost Per Item	Total Cost
(a)	**Cricket Practice Pitch Surface** Supply 10 mm thick dense, Knit De Knit polypropylene fibers surfaces cover concrete surface Cricket pitch either permanent or roll out installation, pile Height 10mm Pile Weight 800 gsm size 3 x20m. Coating Weight 800 gsm Product Weight 1770 gsm Tuft Gauge 3/16" stitch Rate 34/10cm pitch area = 3.6M wide x 25 Mtr length x 3 Nos Spike Test as per NF P 90-101 not less than 30,000 cycles of resistance, supply and laying of WBM stone aggregate/brick blast thickness up to 150mm and compact with watering and rolling. Concrete flooring: Plain cement concrete (M 7.5) 1:4:8 of thickness 75mm in cricket practice pitch and also including the cost of centering shuttering complete & finishing the surface with smooth finish.	Sqft	682		
(b)	**Cricket Practice Pitch Cage** Three Bay size 3.66M Wide x 28.8 mtr, 42 mm diameter x 3mm galvanized steel uprights and top rods. 3.66mlong top rods complete with 11 net hanging hooks. 450 mm deep steel sockets fitted with stabilizing base plates. A heavy duty tube clamp is supplied with each upright. Garware HDPE net 1.5 mm thick. Supplying & installation of cricket tournament 45 x 45 x 2.5mm net height will 18 feet in 4 side of cage. Color green . UV Resistant Poles. 48OD MS Poles verticals. 4848 OD Poles Horizontal (Top & Bottom). Shape – Round. 1 cpat primer & 2 coat enamel painted (bus green color),. Vertical Pole to pole distance 12 feet to 15 feet. Top & bottom horizontal pipe will be Apollo, Surya, Jindal any ISI branded market.	Sqft	682		
(c)	**Renovation of Existing Cricket Pitch** Leveling and removing of plants and cleaning of sand, filling of new soil to level the floor.	Sqft	682		
	Total				

2. Total cost (including all taxes) to be mentioned should be all inclusive. No additional payment will be made.

3. 5% of the total cost will be retained in the form of Joint FD/Bank Guarantee as security deposit by the final bidder and the same will be refunded on completion of one year/warranty period.
fsfac

4. Firm to ensure work to be executed as per above scope of work.

5. All quotation documents will be signed by the authorized firm's representative and firm's rubber stamp will be affixed on all the pages of the documents including envelope in which the quotation document will be sealed.

6. "Quotation for **"Construction of Cricket Practice Pitch "** will clearly be mentioned on top of the envelope.

7. Payment will be made by cheque after verification by the Project Management Group.

8. Photocopy of GST Registration and PAN Card will be attached with the quotation.

9. Firms to mention their full address with telephone number on the envelope.

10. Time Period for execution of job - Within 30 days on issue of supply order.

11. If the requisite items will not be supplied in the prescribed period ie 30 days, then firm has to apply in writing with valid reasons for extension of supply period which will be accorded by the chairman for 5 days only, thereafter necessary penalty will be levied as under :-

(a) 1% Liquidated Damages will be deducted upto 10 days.

(b) Thereafter 2% penalty will be levied for every 10 days or part thereof.

12. Written request seeking any extension in PDC should came to Chairman minimum 7 days in advance with valid reasons. The extension of PDC can be accorded by Chairman for 5 days only. Decision on grant of extension in PDC will entirely be at the sole discretion of Chairman.

13. **Pre-Bid Meeting/Interaction**. A pre bid meeting/interaction will be held for all interested vendors on **22 Feb 2025** at 1100 hr at Army Public School, Jodhpur. Pre Bid meeting attendance is **compulsory** for all participating bidders for the said quotation.

14. In view of the above, you are requested to intimate your quotation. Your quotation in a sealed cover addressed to the Principal, Army Public School Jodhpur should reach this office by 1100 hrs on **27 Feb 2025**. The quotation will be opened at **1115** hrs on **27 Feb 2025**.



(Dr (Mrs) Tabassum Khan)
Principal

To be filled by the Firm before Submission of Quotation

Name & address of the firm : _____

_____

TIN No (Compulsory) _____

GST No (Compulsory) : _____

Name of the Firm's owner/Rep _____

Signature of the firm's owner/rep with seal : _____

Telephone & Mobile No : _____

E-mail address of the Firm : _____

Date of Depositing of the Quotation : _____